

マイルド浸透シーラー

工程間 2h

希釈率 0%

標準塗付量 0.1~0.15kg/m²/回

適用

0.13 kg/m²

主剤	硬化剤	総重量	塗付面積
14 kg	1 kg	15.0 kg	115.4 m ²
12.6 kg	0.9 kg	13.5 kg	103.8 m ²
11.2 kg	0.8 kg	12.0 kg	92.3 m ²
9.8 kg	0.7 kg	10.5 kg	80.8 m ²
8.4 kg	0.6 kg	9.0 kg	69.2 m ²
7 kg	0.5 kg	7.5 kg	57.7 m ²
6.3 kg	0.45 kg	6.8 kg	51.9 m ²
5.6 kg	0.4 kg	6.0 kg	46.2 m ²
4.9 kg	0.35 kg	5.3 kg	40.4 m ²
4.2 kg	0.3 kg	4.5 kg	34.6 m ²
3.5 kg	0.25 kg	3.8 kg	28.8 m ²
2.8 kg	0.2 kg	3.0 kg	23.1 m ²
2.1 kg	0.15 kg	2.3 kg	17.3 m ²
1.4 kg	0.1 kg	1.5 kg	11.5 m ²
1260 g	90 g	1,350 g	10.4 m ²
1120 g	80 g	1,200 g	9.2 m ²
980 g	70 g	1,050 g	8.1 m ²
840 g	60 g	900 g	6.9 m ²
700 g	50 g	750 g	5.8 m ²
560 g	40 g	600 g	4.6 m ²
420 g	30 g	450 g	3.5 m ²
280 g	20 g	300 g	2.3 m ²
140 g	10 g	150 g	1.2 m ²